

CUSTOM SWIMMING POOL PROPOSAL FOR:

Chris and Kathy Chang 19 Verdant Valley Place The Woodlands, TX, 77382

May 23, 2019

Prepared By: Chris Heinze Ph: 713.927.9674 Email: chrisH@codypools.com

We are pleased to provide our proposal for the construction of a custom pool for your Residence. The following scope of work is listed below:

General Specifications

		TOF
Pool Dimensions:	17' x 32'	
Pool Perimeter:	98 ft	
Pool Surface Area:	<mark>544 sqft</mark>	
Pool Depth:	<mark>3ft x 4ft x 5ft</mark>	
		APSP
Spa Dimensions:	N/A	The Association of Pool & Spa Professionals™
Spa Perimeter:	N/A	MEMBER
Spa Surface Area:	N/A	
Spa Raised:	N/A	
Spa Depth:	N/A	Awards (
		Excellence
Total Gallons:	13,860 (adju	isted for tan shelf)

S S



Phase One - Approvals

City Permit:	All fees and inspections included, as required by the city
Home Owners Assoc:	Assistance with required plans and forms, Fees by buyer
Insurance:	\$2,000,000 General Liabilty and Workers Compensation Insurance provided.
Standards:	Design meets current standards as detailed by ISPSC guidelines.
Plans:	Final construction plans will be supplied for approval.
Layout:	Design will be marked in yard for approval.

Phase Two - Excavation

Fence:	Removal and Replacement of fence as required.	
	Side Gates will be corrected to meet Code Compliance	
Access:	Standard clearances required.	
Rock:	Hard rock excavation charged at \$250 per hour. 0 hours included.	
Material:	All excavation material to be hauled away, unless specified	
Additional:	N/A	

Phase Three - Steel & Gunite

3/8 inch Steel Rebar on 10 inch Centers, bot	th ways.
1/2 inch Steel Rebar X 4	
N/A	
Dry Mix Gunite rated to exceed APSP Buildi	ng Standards
12" Bond Beam, 6-8" Walls/Floor	All elevated/exposed walls to be 12"
	1/2 inch Steel Rebar X 4 N/A Dry Mix Gunite rated to exceed APSP Buildi





Phase Four - Plumbing & Electrical

Plumbing Note: Your pool plumbing system is designed with safety as the primary consideration. All suction and pressure, (fixtures and fittings) which we install shall conform to the manufacturers flow rate specifications. In addition, all suction fixtures are connected to a secondary fixture to provide for suction RELIEF FLOW. Main drains are fitted with VGB approved safety drain covers, which are to remain in place at all times. The complete plumbing system shall be assembled and pressure tested throughout the construction process. Plumbing is assembled and configured to balance the suction and pressure side for flow efficient operation.

Pool Pipes: Returns: Skimmers:	2 inch Schedule 40 PVC. (4) Directional flush mount inlets, placed for maximum efficiency. (2) Aquastar, Indepenendently plumbed for optimum c <u>ontrol.</u>		
Drains:	(2) 10 inch SDX, VGB compliant Anti - vortex; and		
	-	anti - entrapment	
Spa Pipes:	N/A		
Spa Jets:	N/A -		
Spa Air:	N/A		
Spa Drain:	N/A		
Fill Line: Overflow Line: Cleaner Line:	N/A included (1) Independently plumbed		
Gas Line:	N/A		

Electrical Note: Cody provides for the complete electrical connection of all lighting and equipment, which includes all linear footage of in-ground service w/all terminations, grounding, bonding, and mechanical installation. All electrical work shall meet local and national standards to include the installation of ground fault interrupters. All lighting and mechanical equipment is bonded and grounded for safety, and all testing and safety inspections are provided.





Phase Five - Stone & Tile

Pool/Spa Tile:	6" Band at waterline, Frost-proof -	Std Selection
Pool Coping:	#N/A	
Spa Coping:	N/A	
Spa Facing:	N/A	
Raised Beam:	N/A	
Boulders in Beam:	N/A	

Phase Six - Water Features

Boulder Waterfall:	-
Magicfalls - Sheer:	N/A
Wok Pots:	N/A
Stone Scuppers:	N/A
Deck Jets:	N/A
Laminar Jets:	N/A
Wall Sconce:	N/A
Bubbler - 1 Nozzle:	N/A
Parascope:	N/A
Other:	N/A
Spa Spillway:	N/A
Negative Edge:	N/A

Phase Seven - Decking & Walls

Reinforcement:	3/8" Rebar 16" On Center, 4" Crushed Base, 3/8" Mastic Joint
Deck Material #1:	591 sqft of Brushed Concrete - no color
Deck Material #2:	N/A
Topping:	N/A
Steps:	N/A
Turndown:	15 sqft of 6 inch beam included
Deck-O- Drain:	N/A
Drainage Pipe:	187 ft of total sleeves, to be used with immediate pool area.
VB / Umbrella Sleeves:	N/A
Retaining Walls:	N/A





Phase Eight - Interior

Pool/Spa Interior Finish:	Pebble Sheen - Cody White	Hardens to 15,000 psi; 15 year warranty	
Entry:	93 sqft Custom Tanning Shelf		
Benches:	(5) lf total		
Start-Up:	Complete start-up chemicals for balance and stabilization		
Maintenance:	16' Telescopic Pole, Vacuum Head & Hose, Brush, Net, Test Kit & Thermometer		
Clean Up:	1 load of fill, spread.		

Cody Pools shall provide a complete poolside turnover demonstration, ("pool school") to instruct the owners upon the proper care, safe use, and maintenance of the installation. The finished project shall be cleaned and detailed with all construction debris removed from site.

Equipment

Primary Pump:	Pentair WhisperFlo 1 HP	Saves money!
Feature Pump #1:	N/A	
Feature Pump #2:	N/A	
Filter:	Pentair Clean & Clear 420 Cartridge	
Heater/Chiller:	N/A	
Air:	N/A	
Cleaner:	Pentair Racer LS w/ booster	Easy to clean!
Control Box:	Pentair EasyTouch P-4	
Remotes:	N/A	Easy to operate!
Sanitizers:	In-Line Chlor	Easy to maintain!
Additional Actuators:	0 additional	
Pool Lights:	(1) Pentair GloBrite LED 12v - Pool	Rated to last 10 yrs or 100k hours!
Spa Lights:	(1) Pentair GloBrite LED 12v - Spa	85% more energy efficient!
Step/Deck Lights:	N/A	
Other:	N/A	
Poured/Precast Pad:	Gunite Equipment Pad	





Warranties

Gunite Shell: Equipment: Plumbing: Decks: Tile/Coping: Light: PV3 Infloor Heads: Pebble Plaster: Controls:

Lifetime	
3 Year (parts	& labor)
2 Years	
2 Years	
2 Years	
3 Years	
Lifetime	
15 Years	
3 Years	

By Owner/Others

- Reroute sprinkler and utility lines if required
- Landscaping, Grass or Mulch
- Modification or Upgrade to existing electrical and/or gas meter/service panel
- Gutters and Gutter Drain Pipes
- Supply accurate survey to property
- Water supply for filling of pool and gunite process





Total Investment

List Price:	<mark>\$58,110</mark>	-5,229	
Cody's 2019 winter savings:	-\$5,811		
		Total: 47,070	
Proposed Contract Amount:	\$52,299		
Payment Schedule:	40% upon completic	40% upon completion of Excavation	
	30% upon completic	30% upon completion of Gunite	
	20% upon completic	n of Decks	
	10% prior to Plaster		
Timeline:	After completion of excavation, co	onstruction time is estimated at	

Recommended Options

Paramount PV3 In-Floor Cleaning and Circulation System

The ultimate in pool cleaning. Pop-up nozzles built into the pool during construction will clean debris from steps, benches, fountain walls and spa. Virtually undetectable when not in use, each nozzle pushes debris from the corners of the pool in a series toward a MDX debris removal drain. Large debris is then trapped in a canister before passing though the filter system.

60 working days or less, barring time delays out of contractors control.

Paramount ULTRA UV System

Adding a ULTRA UV sanitizer to your pool or spa will provide 99.99% contaminant-free water while reducing the use of chemicals. Trident UV units deactivate bacteria, germs, viruses, and algae, thus reducing maintanence costs dramatically and prolonging the life of your pool and equipment

Pebble Sheen Interior Finish (Level 1)

Pool finish provides the exquisite appearance of fine polished stone, creating a stunning, visual effect. Pebble Sheen is developed by combining smaller vibrant, naturally colored stones of many stunning color combinations. Every Pebble Sheen finish is lightly buffed to ensure a smooth and beautiful appearance.

Custom Option

Type Description Here

\$6,111

\$896

\$1,086

\$0

