



11007 Glenora Dr Houston Tx 77065

Www.rivaspoolsdesign.com / rivaspooldesign832@hotmail.com Office: 832-909-4607  
Date: 06-18-2020 [REDACTED] Narcisa Parrales: 281-673-6054  
[REDACTED] Andres Rivas: 832-279-1233

ADDRESS : 18307 Argyle Park Trace, Richmond, TX 77407

## OVERVIEW OF POOL SPECS

- Pool Size : 42'0" x 22'0" (dig) ; 40'0" x 20'0" (swim)
- Capacity: - 22,168 gallons (pool)
- Depth: 3'6" to 5'-0" to 7'0"
- Pool Area : 924 SQFT (dig); 800 SQFT ( swim)
- Pool Perimeter : 124 ' ( dig ) ; 120 ' ( swim )
- Pool Interior : ( Pebble Sheen Level 1 Finish )  
Sheen: Blue Granite, Aqua Blue, Blue Surf, Bordeaux, Caribbean Blue, Desert Gold, French Grey, Irish Mist, Tahoe Blue, White Diamonds ==Selected Aqua Blue==
- Pool coping : Travertine
- Pool Tile : Water Line Tile Travertine
- Pool Type : Geometric
- Pool steps: 3 pool steps included
- Oversized Pool Sun-Shelf 12" D
- (4) Floating step-pads 18 ft
- Pool Raised Beam : 18 "ht. x 15 ft / Finish Split Face Travertine
- Pool Raised Beam : 6 "ht. x 31 ft / Finish Split Face Travertine
- (2) Pool Columns Raised 24"ht.x 18"x18" with (2) mini jets
- Pool Raised beam With 4' Sheer descent

## EQUIPMENT

- Pool: (2) Pentair LED color lights
- Pentair EasyTouch System pool/spa and Waterfall 4 circuit
- Pentair Screenlogic Bundle – Wireless Connection Interface
- Pentair pressure side Racer cleaner (Polaris 280)
- Pentair pressure side racer pump
- Pentair 1 Pool INTELLIFLO VFT
- Pentair Cartridge Filter 420 sq
- Pentair Chlorinator , 320 in line
- Pentair Autofill.
- Pentair 2 Skimmer
- Overflow drain
- Pentair Master Temp Pool Heater



11007 Glenora Dr Houston Tx 77065

Www.rivaspoolsdesign.com / rivaspooldesign832@hotmail.com Office: 832-909-4607

Date: 06-18-2020

Narcisa Parrales: 281-673-6054

Andres Rivas: 832-279-1233

### **CONSTRUCTION INFORMATION**

- STEEL: Bond Beam ( 4 BAR # 4) and ( Floors and walls 8" o.c Bar # 3)
- Gunitite : Bond beam ( 12" width ) and ( floors and wall 8" width )
- Plumbing: all the plumbing equipment is schedule 40 PVC piping master (2") and (1.5")
- Electric: electric shall including hook-up and pump underwater lights (schedule 40PVC) and time clock from existing panel, panel electrical bonding of pool, ground fault interrupter for under water lights
- **Rivas pool Designs, will provide daily and final cleaning of the project**
- Drains : We put drains in the area of the deck and the back of the deck ( Drain PVC # 4" )
- **Fix Sprinkler System and New Grass affected by NEW Construction/Construction access**

