



26302 Penguin St.
Magnolia, TX 77355
TPCL #11677 • CA #33492
(281) 356-5454
www.gemcopeservices.com

TEXAS DEPT OF AGRICULTURE
STRUCTURAL
PEST CONTROL SERVICE
P. O. Box 12847
Austin, TX 78711-2847
(512) 305-8250

DATE: 2/19/2021 TIME: _____ OUT: _____ ACCOUNT NO. _____ ROUTE NO. _____

NAME: Mrs Driskill ACCOUNT TYPE: REGULAR RESIDENTIAL INDOOR
ADDRESS: 167 B Bracebridge 1-TIME COMMERCIAL OUTDOOR
CITY, STATE, ZIP: _____ FREQUENCY: ANNUALLY 6 MONTHS 3 MONTHS

PHONE: _____ MONTHLY BI-MONTHLY WEEKLY

INSPECTION TREATMENT APPLICATION METHOD: _____ APPLICATION RATE: _____

TARGET PEST(S): _____ SITE TREATED: _____

Silk worm

CHEMICALS USED	AMOUNT	%	EPA NUMBER
Cyzone	5.60L	10%	
Nyban bait	6oz	10%	
Fog - Py	PyReth 1%		

DESCRIPTION / REMARKS: - old case removed -
- wasps on web
- worm - service call
- 2 month wasps

SUB-TOTAL	65.00
TAX	5.69
TOTAL	
ACCOUNT BALANCE	
CASH AMOUNT PAID	
CHECK #	
BALANCE DUE	74.69

SERVICED BY: _____ LICENSE NO. _____
CUSTOMER SIGNATURE: _____

REQUESTS: #16

SERVICE ORDER / INVOICE pd 2/19/2021 25629

GAF Timberline Natural Shadow



Cash/Check Discounted Price
(Financing available w.a.c.)

\$17,984.12

Standard Warranty


50-Year Manufacturer

5-Year Labor / Workmanship



Scope of Work & Installation Standards

- **Schedule:** project completed during optimal weather forecast
- **Insurance:** Liability insured (copy available on request)
- **Tear off:** all existing layers of shingles & underlayment removed, including rotten decking as identified
- **Decking:** 3 sheets replaced as needed (\$75 p / sheet thereafter)
- **Perimeter:** Painted Aluminum Drip Edge & GAF Pro Starter installed around all eaves and rakes
- **Underlayment:** Synthetic felt used over entire decking
- **'GAF Royal Sovereign'** shingles on all Hips & Ridges.
- **New plumbing boots w / metal bases** used on all PVC pipes
- **Fasteners:** 1.25" Galvanized Coil Nails, installed with Gauged Pneumatic Guns - 4 nails p / shingle & 6 nails on steep / high areas)
- **Ventilation:** GAF Cobra III Ridge Vents on all ridges > 4LF.
- **Flashings:** Headwall flashing re-secured, sealed, & painted to match roof shingles and prevent rust. New Step Flashing on all sidewalls behind siding / stucco.
- **Completion:** Thorough clean up using magnets to collect nails. All excess debris & materials removed.
- **Local office building:** 25315 Oakhurst Dr., Spring, TX 77386.



installer 3/8/21

