




FLATWORK	B.L. BUILDING LINE	T.O.F. TOP OF FORM	U.V.E. UNOBSTRUCTED VISIBILITY EASEMENT	MANHOLE
PROPERTY LINE	B.L.(FL) FRONT LOAD BUILDING LINE	U.E. UTILITY EASEMENT	M.A.C.C.E. MAINTENANCE & ACCESS EASEMENT	GRATE DRAIN
BUILDING LINE	B.L.(SI) SWING IN BUILDING LINE	W.L.E. WATER LINE EASEMENT	ACC.E. ACCESS EASEMENT	PAD MOUNTED TRANSFORMER
EASEMENT	B.L.(GC) 3 CAR GARAGE BUILDING LINE	ST.M.S.E. STORM SEWER EASEMENT	A.E. AERIAL EASEMENT	TELEPHONE PEDESTAL
WOODEN FENCE	G.B.L. GARAGE BUILDING LINE	S.S.E. SANITARY SEWER EASEMENT	D.E. DRAINAGE EASEMENT	GAS METER
WROUGHT IRON FENCE	(B.G.) BUILDER GUIDELINES	R.O.W. RIGHT-OF-WAY	E.E. ELECTRIC EASEMENT	CABLE PEDESTAL
CHAIN LINK FENCE	F.F. FINISHED FLOOR	P.A.E. PERMANENT ACCESS EASEMENT	WATER VALVE	WATER METER
OVERHEAD ELECTRIC	EXT. EXTENDED	P.U.E. PUBLIC UTILITY EASEMENT	FIRE HYDRANT	MANHOLE & INLET
	PROP. PROPOSED	P.V.T. PRIVATE	MONUMENT	INLET
	C.M. CONTROL MONUMENT	F.N.D. FOUND	IP. IRON PIPE	VAULT



TOTAL LOT	7800.0	SQ. FT.
HOUSE SLAB	3172	SQ. FT.
BUILDING COVERAGE	40.67%	
IMPERVIOUS COVERAGE	48.05%	
FRONT SOD	162	SQ. YD.
REAR SOD	317	SQ. YD.
TOTAL SOD	479	SQ. YD.
FRONT FENCE	10.1	LIN. FT.
LEFT FENCE	88.2	LIN. FT.
RIGHT FENCE	87.5	LIN. FT.
REAR FENCE	60.0	LIN. FT.
TOTAL FENCE	245.8	LIN. FT.
TOTAL FLATWORK	1024	SQ. FT.
DRIVEWAY	440	SQ. FT.
PRIVATE WALK	104	SQ. FT.
APPROACH	196	SQ. FT.
PUBLIC WALK	252	SQ. FT.
A/C PAD	32	SQ. FT.

FLOOR AREA RATIO (FAR)	0.29
FOOTPRINT	3172 SQ. FT.
TOTAL LOT	7800.0 SQ. FT.
SLAB COVERAGE	40.67%
IMPERMEABLE LOT COV.	48.05%

**4910
SABINE TERRACE DRIVE
(50' P.A.E./P.U.E.)(PVT.)**

**PLOT PLAN
SCALE: 1" = 20'**

NOTES:
 1. ALL BEARINGS SHOWN HEREON ARE BASED ON THE RECORDED PLAT.
 2. SURVEYOR HAS NOT ABSTRACTED THE SUBJECT PROPERTY. ABSTRACTING BY TITLE COMPANY ONLY. ALL EASEMENTS, RESTRICTIONS AND OTHER MATTERS OF RECORD KNOWN TO SURVEYOR ARE SHOWN AND ARE BASED ON THE RECORDED PLAT AND/OR TITLE REPORT. ALLPOINTS LAND SURVEY, INC. IS NOT LIABLE FOR ANY DAMAGES DUE TO INFORMATION NOT PROVIDED TO SURVEYOR OR BUILDER PLACING ANY IMPROVEMENTS WITHIN A BUILDING LINE OR EASEMENT.
 3. FLATWORK AND FENCING ARE FOR ILLUSTRATION PURPOSES ONLY. REFER TO MUNICIPALITY, HOA, POA, BUILDER GUIDELINES, DEED RESTRICTIONS, DEVELOPMENT PLANS (WSD'S) OR LOCAL CODE FOR REQUIREMENTS. SPECIFIC INSTALLATION REQUIREMENTS TO BE VERIFIED BY BUILDER.
 4. MINIMUM FINISHED FLOOR REQUIREMENTS ESTABLISHED BY FEMA, LOCAL GOVERNMENT AUTHORITIES AND/OR DEVELOPMENT PLANS (INCLUDING APPLICABLE BENCHMARKS/DATUMS AND ADJUSTMENTS) ARE SUBJECT TO CHANGE DURING CONSTRUCTION PROCESS AND SHOULD BE VERIFIED BY BUILDER BEFORE PROCEEDING WITH EACH PHASE OF CONSTRUCTION. PROPOSED FINISHED FLOOR HEIGHTS ABOVE TOP OF CURB ARE CALCULATIONS FOR DRAINAGE PURPOSES TO BE ADJUSTED BASED UPON ACTUAL LOT CONDITIONS AND DO NOT ESTABLISH A MINIMUM FINISHED FLOOR.
 5. LANDSCAPING COMPLIES WITH CITY OF SUGARLAND REQUIREMENTS OF 1 TREE FOR EVERY 50' OF LOT WIDTH IN FRONT YARD.
 6. POST IN HOLE FENCE INSTALLATION.
 7. FINISH FLOOR ELEVATION SHALL BE A MINIMUM OF 1.5' ABOVE BFE, 1' ABOVE TOP OF CURB AND 1.5' ABOVE NATURAL GROUND OR, IF APPLICABLE, AS INDICATED ON INDIVIDUAL LOT, WHICHEVER ELEVATION IS HIGHER PER RECORDED PLAT.

FOR: TAYLOR MORRISON HOMES
 ADDRESS: 4910 SABINE TERRACE DRIVE
 ALLPOINTS JOB#: TM290693 BY: JC
 G.F.:
 JOB:

**LOT 8, BLOCK 3,
HAGERSON ROAD TRACT, SECTION 3,
PLAT NO. 20210090, PLAT RECORDS,
FORT BEND COUNTY, TEXAS**



FLOOD ZONE: X SHADED
 COMMUNITY PANEL:
 48157C0290L
 EFFECTIVE DATE: 04/02/2014
 LOMR: 20-06-1722P | DATE: 6/23/2021

"THIS INFORMATION IS BASED ON GRAPHIC PLOTTING. WE DO NOT ASSUME RESPONSIBILITY FOR EXACT DETERMINATION"

ISSUE DATE: 2/23/2022

©2022, ALLPOINTS LAND SURVEY, INC.
All Rights Reserved.