

Scope of Work

EXHIBIT "A" SCOPE OF WORK/ESTIMATE

REPLASTER EXISTING POOL WITH MINI PEBBLE STONESCAPES
ADD SECONDARY MAIN DRAIN FOR CODE COMPLIANCE
REPLACE EXISTING POOL TILE WITH 6X6 STANDARD WATERLINE TILE
REPLACE EXISTING POOL COPING WITH 12X12 TRAVERTINE COPING
BUILD RAISED WALL FACED WITH 2X4 TRAVERTINE SPLIT FACE STONE
ADD 3 TRAVERTINE STONE SCUPPERS FOR WATER FEATURE
INSTALL RAINBOW 320 INLINE CHLORINE FEEDER
INSTALL 1.5HP PENTAIR POOL PUMP FOR WATER FEATURE
INSTALL PENTAIR UV SYSTEM
INSTALL PENTAIR INTELLIBRITE LED POOL LIGHT
INSTALL LOW VOLTAGE TRANSFORMER
TEAR OUT 560 SQ FT OF EXISTING POOL CONCRETE
POUR 560 SQ FT OF NEW CONCRETE WITH 16" ON CENTER STEEL
WITH 3000 PSI, 4" THICKNESS
ADD DECK DRAINS RAN TO STREET
TIE IN GUTTERS TO DECKING DRAINS
TOP CONCRETE WITH SPRAY DECK
RUN NEW PLUMBING 1.5' SCHEDULE 40 PVC FOR WATER FEATURES

****PRICE INCLUDES ANY PERMIT REQUIRED****