



Handwritten signature and a circular stamp containing the number '12'.



CALCULATION SUMMARY:
TOTAL NUMBER OF BEDROOMS: 4 (UNDER 3,500 SQ. FT.)
O = 300 G.P.D. (375 G.P.D. MINUS 75 FOR USE OF L.F.F.) 6489'
APPLICATION RATE/ 0.241 GALLONS/SQ.FT./DAY
TOTAL SPRAY AREA REQUIRED = 7,217 sq.ft.
TOTAL SPRAY AREA DESIGNED = 7,209 sq.ft.
INSTALL 3 FURFLE TOP SPRAY HEADS WITH APPROPRIATE LOW ANGLE NOZZLES.
HEADS SHALL NOT EXCEED 40 FEET WITH INSTALLED NOZZLES TO SPRAY A 20'R
SPRINKLER TIER SHALL BE SET TO SPRAY BETWEEN MIDNIGHT AND 5:00 AM.
INSTALL A 0.5 H.P. PRO FLO SUBMERSIBLE PUMP (OR EQUIV.)
DESIGN BASED ON FINDINGS BY SITE EVALUATOR