INVOICE

Date: May 6, 2022 Invoice # 1799

STW Engineering, PLLC F-14496 5962 FM 1624 Lexington, Tx 78947 979-224-7748 S.travis.weiser@gmail.com TO

000 Little Berry Road, Somerville, Texas 77879

SALESPERSON	JOB	PAYMENT TERMS	DUE DATE
		Due on receipt	

YTC	DESCRIPTION	UNIT PRICE	LINE TOTAL
	OSSF Burleson County Residential Design	\$300.00	\$300.00
		SUBTOTAL	\$300.00
		SALES TAX	
		TOTAL	\$300.00

Make all checks payable to STW Engineering, PLLC **Thank you for your business!**



Burleson County Environmental Office 100 West Buck St, Suite 303, Caldwell TX, 77836

Phone: (979) 567-2360 Fax: (979) 567-2371

(Office use only)						
PERMIT NUMBER						
Payment Receipt Number						

date

APPLICATION FOR AN ON-SITE SEWAGE FACILITY

All information on this form is required. If the installer does not request a construction inspection by the permitting authority within one year of the issuance of the authorization to construct, the authorization to construct expires, and the owner will be required to submit a new application and application fee before an OSSF can be installed. All systems require a construction inspection before a License-to-Operate is issued. License-to-Operate is required before OSSF is put into service. Fees subject to change. Reason for Permit (check one) 🗌 New Construction 🔠 System Replacement 💢 System Repair/Modification 🖂 Transfer of Ownership 🤲 Phone: Owner Name: Site Address: 000 Little Berry Road city/State: Somerville, Texas zip: 77879 City/State: Mailing Address: (if different) Structure Type: ☐ Structure on Slab ☐ Mobile Home ☐ Pier & Beam Other: Living Area Sq Ft.Less Than 2500 SF Year Structure Built: Number of Bedrooms: 3 Number in Household: Water Saving Devices: ☐ Yes ☐ No Name of water company or private well? **Enchanted Oaks Park** ___ Lot: 91 Subdivision Name: (if applicable) Property ID: 25303 Is this property in the floodplain?

YES

NO The Parcel ID is available from the Burleson County Appraisal District Is this property the applicants homestead?

YES

NO Directions to Property: I certify that the above statements are true and correct to the best of my knowledge. Authorization is hereby given to the BURLESON COUNTY DESIGNATED REPRESENTATIVE (DR), the authorized agent for Texas Commission On Environmental Quality (TCEQ), to enter upon the above described property for the purpose of lot evaluation and inspection of the on-site sewage facility and that a license-to-operate the facility will be granted following successful inspection of the installed system which indicates that the system was installed in compliance with the Texas Commission On Environmental Quality (TCEQ) On-Site Facility Rules, TAC30, Chapter 285. Signature of Owner: Site Evaluator Name: Travis Weiser Installer Name: Provide installers name NOT the company name License #: 107845 Phone #: 979-224-7748 License #: Phone #: Installer Email: Designer Name: Travis Weiser License #: (RS or PE) 107845 Phone #: 979-224-7748 Installer please write in GPD next to system type Evapotranspiration Bed: Standard Trench/Bed: Leaching Chamber: Surface Application: Drip Irrigation: Pumped Effluent: Gravel-less Pipe: EZflow System: PTI System: Low Pressure Dosing: Absorptive Mound: Other: OFFICE USE ONLY Repair \$100 Re-Inspection \$165 Modification \$165 Residential \$330 Commercial \$540 ref#__

MODIFICATION - OSSF systems with current permit on record; modification includes any changes that add to or take away from the original design of the OSSF system

REPAIR -OSSF systems with current permit on record in need of repair due to collasped lines, tanks, etc. Repairs do not alter the original design of the OSSF.

		OSSF SOIL	EVALUATION	FORM	
Date Performed: 4/26/22			Property Location: Little Berry Road, Somerville, Texas		
Site Evaluator: Travis Weiser			Proposed Excavation Depth: 5'		
of the Locati excava	st two soil excava proposed dispose on of the soil bo ation depth, or to	ntions must be performed al area. ring or dug pits must b restrictive horizon. For con and identify any resti	e performed to a dep surface disposal, the s	oth of at least two fe surface horizon must	eet below the proposed be evaluated.
Soil Borin	g Number:				
Depth (inches)	Texture & Classification	Drainage (Mottles/Water Table)	Restrictive Horizon	Gravel Analysis	Observations/Notes
0" 12" 24" 36" 48" 60"	Brown Loan	None	No	6%	
72"					
Soil Borin	g Number:				
Depth (inches)	Texture & Classification	Drainage (Mottles/Water Table)	Restrictive Horizon	Gravel Analysis	Observations/Notes
0" 12" 24" 36" 48"			Same		
72"I hereby certificability.	y that the findings	s of this report are based	d on my field observati	ions and are accurate	e to the best of my
Site Evaluator	Name: Travis W	/eiser (printed)	Signature:	()"	

1705 04192011

Date:

Site Evaluator License #: 107845

Travis Weiser, PE 107845 STW Engineering, PLLC F-14496 5962 FM 1624 Lexington, Tx 78947 979-224-7748 s.travis.weiser@gmail.com

May 6, 2022

Job # 1799

Name:

Address: 000 Little Berry Road, Somerville, Texas 77879

County: Burleson

Subdivision: S2507 ENCHANTED OAKS PARK LOT 91 0.5825 ACRES

Notes:

Design Parameters:

Septic Tanks: 1- 1000-gal Two Compartment Treatment tank

Pump Tank: NA

Select Fill: Use existing class II soil

Gravel: 18 CY (3/4 inch to 2 inch Washed, Clean, and Graded Gravel)

Laterals: 240 ft (4" Sch 35 Perforated Pipe) Distribution: 30 feet (4" SCH 40 PVC) Casing Pipe: NA (6" SCH 40 PVC)

Valves: Pump:



House Details

Number of Bedrooms: 3

Square Footage: Less Than 2500 SF

Drainage: The site has positive drainage, sloping away from the house at approx 1.5%.

Water Saving Fixtures: Yes

Water Supply: Public Water Supply Presence of 100-year Floodplain: No Presence of upper water shed: No

Presence of adjacent ponds, streams, water impoundments: No

Existing or proposed water well in nearby area: Yes Organized sewage service available to lot or tract: No

Evidence of groundwater: No

Daily Flow: 240 gpd

Septic Tank Sizing:

For Q equal to or less than 250 gal/day: V=750 gallons

We will install One - 1000 gallons two compartment for the trash tank.

Soil Details

Soil Class: II

Maximum Load Rate: 0.25

Lateral Design

A = Q/Ra

Q = 240 gpdRa = 0.25

A = 240/.25

A = 960 SF

L=(A-2W)/(W+2)

L= (960-2(2))/(2+2) = 239 LF Required and 240 LF Designed

Notes:

- 1. Minimum of 5' between centerline of Lateral piping.
- 2. The lateral distribution lines should be a minimum of 18" below grade and maximum of 36" below grade.
- 3. Tank inlet and outlet tees connections per 30 TAC 285 (tees with extensions to 25-50% of tank depth).
- 4. The bottom of the excavation shall be level to within one inch over each 25 feet of excavation or within three inches over the entire excavation, which is less.
- 5. Trench to have 6" rock below pipe and 6" rock above pipe and a minimum of 6" of Class 1B, II or III soil back filled over rock. Geo-Textile fabric to be placed between the Rock and the imported select file. Or Gravel less pipe can be used as a substitute.
- 6. The media shall consist of clean, washed and graded gravel, broken concrete, rock, crushed stone, chipped tires, or similar aggregate that generally one uniform size and approved by the executive director. The size of the media must range from 0.75 2.0 inches as measured along its greatest dimensions.
- 7. A Two-way cleanout plug must be provided between the sewer stub out and the Treatment tank. Only sanitary type fittings constructed of PVC Sch. 40 or SDR 26 shall be used on this section of the sewer.
- 8. Maintain minimum 1.0% grade in pipes from Septic tank to Drain field.
- 9. Maintain 1/8-inch fall per foot slope between house and Septic Tanks.
- 10. Immediately after completion of installation, homeowner must seed the drainage field with Bermuda **AND** Rye grass, as necessary in disturbed areas, and mow as necessary to maintain optimum growing conditions.
- 11. System is designed in accordance with daily water usage described above. Any usage above designed will invalidate design.
- 12. All pre-cast concrete tanks will meet ASTM C1227-93a, d30 Texas Administrative Code 5.32(a) (1) (F).
- 13. Pipe Bedding. Pipes such as sewer pipes from the structure to the treatment facility and from the treatment facility to the disposal component shall be bedded with four inches of Class IB, Class II, or Class III soil with less than 30% gravel. The bedding soil shall be free of organic material and any rocks or grains larger than ½ inch.
- 14. Tank inlet and outlet tees connections per 30 TAC 285 (tees with extensions to 25-50% of tank depth).
- 15. A minimum of four inches of sand, sandy loam, clay loam, or pea gravel, free of rock larger than ½ inch in diameter, shall be placed under and around all tanks, except poured-in-place concrete tanks. Unless otherwise approved by permitting authority, thank excavations shall be left open until they have been inspected by the permitting authority. Tank excavations must be backfilled with soil or pea gravel that is free of rock larger than ½ inch in diameter. Class IV soil and gravel lager than one-half inch in diameter are not acceptable for use as backfill material.
- 16. Installer shall provide risers and tank inspection ports to grade with access safety provisions per 30 TAC 285.38 (9/1/2012). This should include access limitation (>65-lb lid or hardware secured lid) and secondary plug, net, or mesh in riser.

Thank You,

Travis Weiser, PE 5962 FM 1624

Lexington, Texas 78947

979-224-7748

s.travis.weiser@gmail.com



