


WILLIAM BAIRD SURVEY, A-10  
WALLER COUNTY, TEXAS

GRAPHIC SCALE



( IN FEET )  
1 inch = 40 ft.

JAMES G. PHELAN  
CALLED 34.377 ACRES  
C.F. NO. 1808613, O.P.R.W.C.T.

P.O.B.  
SET 1/2" CIR  
PICKERING  
R.P.L.S. 5879

N 89°23'00" E-267.70'

SET 1/2" CIR  
PICKERING  
R.P.L.S. 5879

S 31°24'43" E  
114.41'

SET 1/2" CIR  
PICKERING  
R.P.L.S. 5879

S 00°37'00" E-210.93'

2.250 ACRES  
98,010 SQ. FT.

S 89°23'00" W-326.28'

SET 1/2" CIR  
PICKERING  
R.P.L.S. 5879

JAMES G. PHELAN  
CALLED 34.377 ACRES  
C.F. NO. 1808613, O.P.R.W.C.T.

MELLMAN ROAD

N 00°37'00" W-309.21'  
EDGE OF ASPHALT

JAMES G. PHELAN  
CALLED 34.377 ACRES  
C.F. NO. 1808613, O.P.R.W.C.T.

**METES AND BOUNDS DESCRIPTION**

BEING A 2.250 ACRE (98,010 SQUARE FOOT) TRACT OR PARCEL OF LAND SITUATED IN THE THE WILLIAM BAIRD SURVEY, A-10 AND THE JESSE CLARY SURVEY, A-110, WALLER COUNTY, TEXAS, AND BEING OUT OF THAT CERTAIN CALLED 34.377 ACRE TRACT CONVEYED TO JAMES G. PHELAN, RECORDED UNDER CLERK'S FILE NO. 1808613 OF THE OFFICIAL PUBLIC RECORDS OF WALLER COUNTY, TEXAS, SAID 2.250 ACRE TRACT BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS: (BEARINGS ARE BASED ON THE TEXAS COORDINATE SYSTEM, SOUTH CENTRAL ZONE 4204)

BEGINNING AT A 1/2-INCH IRON ROD WITH CAP STAMPED "PICKERING RPLS 5879" SET IN THE WEST LINE OF SAID 34.377 ACRE TRACT, SAME ALSO BEING THE EAST LINE OF MELLMAN ROAD AND BEING S 00°37'00" E, 537.18 FEET FROM A 1/2 INCH IRON ROD WITH PLASTIC CAP STAMPED "RPLS 2085" FOUND AT THE NORTHWEST CORNER OF THE 34.377 ACRE TRACT;

THENCE, N 89°23'00" E-267.70 FEET TO A 1/2-INCH IRON ROD WITH CAP STAMPED "PICKERING RPLS 5879" SET MARKING THE NORTHERLY NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, S 31°24'43" E-114.41 FEET TO A 1/2-INCH IRON ROD WITH CAP STAMPED "PICKERING RPLS 5879" SET MARKING THE EASTERLY NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, S 00°37'00" E-210.93 FEET TO A 1/2-INCH IRON ROD WITH CAP STAMPED "PICKERING RPLS 5879" SET MARKING THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, S 89°23'00" W-326.28 FEET TO A 1/2-INCH IRON ROD WITH CAP STAMPED "PICKERING RPLS 5879" SET IN THE WEST LINE OF THE AFORESAID 34.377 ACRE TRACT, SAME BEING THE EAST LINE OF SAID MELLMAN ROAD AND MARKING THE SOUTHWEST CORNER OF THE HEREIN DESCRIBED TRACT;

THENCE, N 00°37'00" W-309.21 FEET WITH THE WEST LINE OF THE 34.377 ACRE TRACT, COINCIDENT WITH THE EAST LINE OF MELLMAN ROAD TO THE POINT OF BEGINNING AND CONTAINING 2.250 ACRES (98,010 SQUARE FEET) OF LAND, MORE OR LESS.

**LEGEND:**

- - ELECTRIC BOX
- - TELEPHONE BOX
- - CABLE TELEVISION BOX
- - GAS METER
- - WATER METER
- ☆ - LIGHT POLE
- ⊙ - SANITARY SEWER MANHOLE
- ⊙ - STORM SEWER MANHOLE
- ⊙ - TELEPHONE MANHOLE
- ⊙ - ELECTRIC MANHOLE
- ⊙ - SAMPLE WELL
- ▣ - DRAINAGE INLET
- △ - FIBEROPTICS MARKER
- △ - UNDERGROUND TELEPHONE MARKER
- △ - GAS MARKER
- △ - PIPELINE MARKER
- ⋈ - FIRE HYDRANT
- ⊙ - WATER VALVE
- ⊙ - GAS VALVE
- ⊙ - MONITORING WELL
- ⊙ - UTILITY POLE
- ⊙ - ELECTRIC METER
- ⊙ - TRAFFIC SIGNAL POLE
- ⊙ - TRAFFIC CONTROL BOX
- ⊙ - BENCHMARK
- F.C. - FILM CODE
- C.F. NO. - CLERK'S FILE NUMBER
- W.C.D.R. - WALLER COUNTY DEED RECORDS
- W.C.M.R. - WALLER COUNTY PLAT RECORDS
- POB - POINT OF BEGINNING
- POC - POINT OF COMMENCING
- SQ. FT. - SQUARE FEET
- S.S.E. - SANITARY SEWER EASEMENT
- STM.S.E. - STORM SEWER EASEMENT
- HL&P - HOUSTON LIGHTING & POWER
- ESMT. - EASEMENT
- U.E. - UTILITY EASEMENT
- P- OVERHEAD UTILITY LINES
- X- BARBED WIRE FENCE
- O- CHAIN LINK FENCE
- //- WOOD FENCE
- WROUGHT IRON FENCE

**SURVEY NOTES:**


1. ONLY VISIBLE EVIDENCE OF UTILITIES AND IMPROVEMENTS ARE SHOWN.
2. THE SURVEYOR DID NOT ABSTRACT THE SUBJECT PROPERTY. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF TITLE AND SOME EASEMENTS, BUILDING LINES, RESTRICTIONS, ETC., MAY HAVE BEEN GRANTED BY SEPARATE INSTRUMENTS AND NOT REFLECTED HEREON.
3. NOTHING IN THIS SURVEY IS INTENDED TO EXPRESS AN OPINION REGARDING OWNERSHIP OR TITLE.
4. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS BEST KNOWLEDGE, INFORMATION AND BELIEF.
5. PROPERTY LIES IN ZONE "X" AREAS DETERMINED TO BE OUTSIDE THE 100 YEAR FLOODPLAIN ACCORDING TO THE FLOOD INSURANCE RATE MAP NO. 48473C0075E EFFECTIVE DATE 02-18-09. THIS FLOOD STATEMENT DOES NOT IMPLY THAT THE PROPERTY OR STRUCTURES THEREON WILL BE FREE FROM FLOODING OR FLOOD DAMAGE. THIS FLOOD STATEMENT SHALL NOT CREATE LIABILITY ON THE PART OF THE SURVEYOR.
6. THIS SURVEY IS THE PROPERTY OF PICKERING & ASSOCIATES PROFESSIONAL LAND SURVEYORS LLC, IS CERTIFIED FOR THIS TRANSACTION ONLY AND IS NOT TRANSFERABLE TO ADDITIONAL INSTITUTIONS OR OWNERS. USE OF THIS SURVEY FOR PURPOSES OTHER THAN INTENDED, WITHOUT WRITTEN PERMISSION, WILL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO THE SURVEYOR. NOTHING HEREON SHALL BE CONSTRUED TO GIVE ANY RIGHTS OF BENEFITS TO ANYONE OTHER THAN THOSE CERTIFIED.

**SURVEYOR'S CERTIFICATION**

I, ROGER D. PICKERING A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, DO HEREBY CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND, UNDER MY SUPERVISION OF THE PROPERTY DESCRIBED HEREON (AND/OR BY METES AND BOUNDS ON ATTACHED SHEET), IS CORRECT AND THERE ARE NO ENCROACHMENTS APPARENT ON THE GROUND, AND THAT ALL IMPROVEMENTS LIE WHOLLY WITHIN THE PROPERTY LINES, EXCEPT AS SHOWN OR NOTED HEREON.

WITNESS MY HAND THIS 27TH DAY OF MARCH, 2023

*Roger D. Pickering*  
ROGER D. PICKERING  
REGISTERED PROFESSIONAL LAND SURVEYOR  
TEXAS REGISTRATION NO. 5879



SHEET 1 OF 1	SCALE: 1"=40'	DATE: 03-14-23
	REVISION:	
	BOOK : N/A	
	DRAWN BY: R.D.P.	
	APPROVED BY: R.D.P.	
PROJECT NO.: 70025-23A		

<b>JAMES G. PHELAN</b>
00000 MELLMAN ROAD HEMPSTEAD, TEXAS 77445

<b>BOUNDARY SURVEY</b>
BEING A 2.250 ACRE (98,010 SQUARE FOOT) TRACT OR PARCEL OF LAND SITUATED IN THE WILLIAM BAIRD SURVEY, A-10 AND THE JESSE CLARY SURVEY, A-110, WALLER COUNTY, TEXAS. (SEE ATTACHED METES AND BOUNDS DESCRIPTION)

<b>PICKERING &amp; ASSOCIATES</b> PROFESSIONAL LAND SURVEYORS, LLC
Firm Registration No. 10165200 7702 Pin Oak Street Montgomery, Texas 77316 Phone: (936) 447-4703 Mobile: (281) 804-0785 rpickering@hotmail.com
Copyright 2023